

JAEGER PRODUCTION PLANT

INDUSTRIAL CONSTRUCTION



CONSTRUCTION OF A PRODUCTION AND WAREHOUSE HALL FOR CAR PARTS IN GRYFINO TOGETHER WITH ADMINISTRATIVE FACILITIES, NECESSARY TECHNICAL INFRASTRUCTURE AND LAND DEVELOPMENT.

As part of the investment, a production and warehouse hall was built in a two-span system, with a technological cooler and a paint shop with an individual mechanical ventilation system. The facility is equipped with the following installations: electrical, telecommunication, ventilation, air conditioning, water supply and roof drainage in a vacuum system. In the industrial floor, a system of underground channels distributing cabling for technological devices was made. The administrative and office building with two above ground storeys and a reinforced concrete basement designed for locker rooms and social facilities was also built. A ventilated façade of fiberglass-cement panels with glazing by Aluprof was made. Also, infrastructure around the investment was built - roads, access roads, sidewalks and such external plumbing as: hydrant, water supply, rainwater, sanitary, gas and greenery watering. An external retention reservoir for rain water was also placed, and the investment area was fenced with a system of panels. The total surface of hardened pavements was 12,000 m², and the volume of completed earthworks exceeded 61,300 m³.

INVESTOR: JAEGER POLAND LLC

FORM: GENERAL CONTRACTOR

VALUE: <10 mln 10-20 mln >20 mln

PROJECT DATES: May 2016 – March 2017

